

ETAP

Project:
Location:
Contract:
Engineer:
Filename: first_project

19.0.1C

Page: 1
Date: 06-05-2026
SN:
Revision: Base
Config.: Normal

Bus FDR Loading -2
Loading Category: Design

Bus ID: Bus5

Voltage: 230.00 kV Rating: 0 A, 0 kVA

Connected Feeders & Loads	Description	Status	Nameplate Rating	Absorbed Load	Unit	Operating Loads				Comments	
						% EFF	% PF	kW	kvar		kVA
step_down_transformer		C					80.00	64000.00	48000.00	80000.00	
		I					0.00	0.00	0.00	0.00	
		S					0.00	0.00	0.00	0.00	
Bus Summary						Continuous	80.00	64000.00	48000.00	80000.00	
						Intermittent	0.00	0.00	0.00	0.00	
						Spare	0.00	0.00	0.00	0.00	
						Bus Total	80.00	64000.00	47999.99	79999.99	

Operating Loads = Connected Loads X % Loading
Bus Total Operating Loads include Connected Loads X % Loading X Demand Factor X Diversity Factor (Bus Diversity Factors are applied to directly connected loads only.)
Status: C=Continuous, I=Intermittent, S=Spare, NC=Non-Continuous Panel Loads
Diversity Factors: C: None, I: None, S: None
Nodes are not reported.

Project:	ETAP	Page:	2
Location:	19.0.1C	Date:	06-05-2026
Contract:		SN:	
Engineer:	Bus FDR Loading -2	Revision:	Base
Filename: first_project	Loading Category: Design	Config.:	Normal

Bus ID:	Bus6										
Voltage:	13.80 kV	Rating:	0 A, 0 kVA								
Connected Feeders & Loads	Description	Status	Nameplate Rating	Absorbed Load	Unit	Operating Loads				Comments	
						% EFF	% PF	kW	kvar		kVA
underground_cable		C					80.00	64000.00	48000.00	80000.00	
		I					0.00	0.00	0.00	0.00	
		S					0.00	0.00	0.00	0.00	
Bus Summary						Continuous	80.00	64000.00	48000.00	80000.00	
						Intermittent	0.00	0.00	0.00	0.00	
						Spare	0.00	0.00	0.00	0.00	
						Bus Total	80.00	64000.00	47999.99	79999.99	

Operating Loads = Connected Loads X % Loading
Bus Total Operating Loads include Connected Loads X % Loading X Demand Factor X Diversity Factor (Bus Diversity Factors are applied to directly connected loads only.)
Status: C=Continuous, I=Intermittent, S=Spare, NC=Non-Continuous Panel Loads
Diversity Factors: C: None, I: None, S: None
Nodes are not reported.

ETAP

Project:

19.0.1C

Page: 3

Location:

Date: 06-05-2026

Contract:

SN:

Engineer:

Revision: Base

Filename: first_project

Bus FDR Loading -2
Loading Category: Design

Config.: Normal

Bus ID: Bus7

Voltage: 13.80 kV

Rating: 0 A, 0 kVA

Connected Feeders & Loads	Description	Status	Nameplate Rating	Absorbed Load	Unit	Operating Loads					Comments
						% EFF	% PF	kW	kvar	kVA	
Feeder1		C	40000.00	40000.00	kVA	100.00	80.00	32000.00	24000.00	40000.00	
Feeder2		C	40000.00	40000.00	kVA	100.00	80.00	32000.00	24000.00	40000.00	
Bus Summary						Continuous	80.00	64000.00	48000.00	80000.00	
						Intermittent	0.00	0.00	0.00	0.00	
						Spare	0.00	0.00	0.00	0.00	
						Bus Total	80.00	64000.00	47999.99	79999.99	

Operating Loads = Connected Loads X % Loading

Bus Total Operating Loads include Connected Loads X % Loading X Demand Factor X Diversity Factor (Bus Diversity Factors are applied to directly connected loads only.)

Status: C=Continuous, I=Intermittent, S=Spare, NC=Non-Continuous Panel Loads

Diversity Factors: C: None, I: None, S: None

Nodes are not reported.

Bus ID: TX_substation

Voltage: 230.00 kV Rating: 0 A, 0 kVA

Connected Feeders & Loads	Description	Status	Nameplate Rating	Absorbed Load	Unit	Operating Loads					Comments
						% EFF	% PF	kW	kvar	kVA	
Transmission_Line		C					80.00	64000.00	48000.00	80000.00	
		I					0.00	0.00	0.00	0.00	
		S					0.00	0.00	0.00	0.00	
Bus Summary						Continuous	80.00	64000.00	48000.00	80000.00	
						Intermittent	0.00	0.00	0.00	0.00	
						Spare	0.00	0.00	0.00	0.00	
						Bus Total	80.00	64000.00	47999.99	79999.99	

Operating Loads = Connected Loads X % Loading
Bus Total Operating Loads include Connected Loads X % Loading X Demand Factor X Diversity Factor (Bus Diversity Factors are applied to directly connected loads only.)
Status: C=Continuous, I=Intermittent, S=Spare, NC=Non-Continuous Panel Loads
Diversity Factors: C: None, I: None, S: None
Nodes are not reported.